



Specifications

- 3-Hole Installation
- All Metal Construction

Features

- 1.5 GPM Flow Rate
- All Metal Construction
- Fixed Hub
- Mounting Hardware Included
- 3-Hole Installation
- 4" Centerset and Mini Widespread Combination
- Install With or Without Deck Plate
- Push and Seal Drain
- Pforever Seal Ceramic Disc Valve
- Pforever Warranty®

Code Compliance

Pfister products are designed and manufactured in compliance with the following standards and codes:

- IAPMO Certified
- CSA B125 Certified
- ASME A112.18.1
- NSF 61/9 Annex G (Low lead)
- Cal Green Compliant
- EPA WaterSense Certification 1.5 gpm, 5.7 L/Min
- ADA Compliant-ANSI A117.1 (Lever handles only)



Dimensions

